




Case Study: Pre-Cast Concrete for University Expansion in the USA




Project Details:

- **Location:** Austin, Texas, USA
- **Project Type:** University Expansion - Science Building Addition
- **Construction Material:** Pre-Cast Concrete for Building Envelope and Structural Elements
- **BIM Software:** Revit Structure

Project Brief:

The University was expanding its science department with a new building addition. To meet a tight construction schedule and ensure high-quality construction, the project team opted for pre-cast concrete for the building envelope and structural elements. BIM played a crucial role in managing the complexities of pre-cast construction and facilitating efficient collaboration amongst architects, engineers, and pre-cast fabricators.



Level of Detailing for BIM Modeling:

The BIM model incorporated a high level of detail for both the architectural and structural components:

- **Architectural Model:** Walls, floors, beams, columns, windows, doors, and other exterior elements were modeled with accurate dimensions and material properties. Pre-cast panel connections, including anchorage details, were modeled for coordination with structural elements.
- **Structural Model:** All pre-cast concrete components (panels, beams, columns) were modeled with precise dimensions, weight, and connection details. Reinforcement details for pre-cast elements were also included within the model.

Scope of Work:


The BIM scope of work for this project included:

- Development of a comprehensive 3D model of the entire building using pre-cast concrete components.
- Coordination of pre-cast panel layouts with architectural and structural elements.
- Clash detection to identify and resolve potential conflicts between pre-cast components, MEP systems, and other building elements before construction began.

- Generation of detailed shop drawings for pre-cast fabrication, including reinforcement details and connection specifications.
- Creation of 3D visualizations to support design reviews and communication with stakeholders.

Project Challenges and Solutions through BIM:

- **Coordination of Pre-Cast Elements:** BIM facilitated precise coordination between pre-cast panels, structural elements, and architectural details. Clash detection within the BIM model identified potential conflicts early on, allowing for design adjustments and avoiding costly rework during construction (estimated reduction of rework costs by **20%**).



- **Shop Drawing Generation:** The BIM model served as a central source of information for generating accurate and detailed shop drawings for pre-cast fabrication. This ensured precise pre-cast element dimensions and reduced delays in the construction schedule (estimated reduction in construction schedule by **15%**).

- **Improved Communication:** The shared BIM model provided a platform for seamless communication between architects, engineers, and pre-casters. Real-time access to the model facilitated collaborative decision-making and streamlined the overall project workflow.

Value Addition through BIM:

- **Reduced Construction Errors:** Clash detection in the BIM model minimized errors during pre-cast fabrication and on-site construction, leading to a smoother construction process and reduced rework costs (**20% reduction**).
- **Improved Design Efficiency:** BIM facilitated faster design iterations with pre-cast layouts easily adjusted within the model, allowing for optimized building design.
- **Enhanced Collaboration:** The shared BIM model fostered better communication and collaboration between project stakeholders, streamlining the design and construction process.
- **Reduced Project Schedule:** The use of pre-cast concrete and BIM-enabled shop drawing generation contributed to a faster construction schedule compared to traditional cast-in-place methods (**15% reduction**).
- **Improved Quality Control:** Detailed BIM models allowed for precise pre-cast fabrication and ensured better quality control throughout the construction process.

Conclusion:

This case study demonstrates the significant value BIM offers for university construction projects utilizing pre-cast concrete. By creating a data-rich 3D model, the project team was able to overcome challenges related to pre-cast coordination, improve communication, and deliver a high-quality building addition on time and within budget. The success of this project highlights the growing importance of BIM in pre-cast construction for educational facilities, promoting efficiency, cost savings, and improved project outcomes.